PWG 71

Extra Item Rate List

PROJECT:- Improvements to Drains and Asphalting to Roads at Balaji Layout Near Railway Gate in Ward No:-06 Byatarayanapura Sub Division.

Sl.No.	Item of Work	Unit	Approximate Quantity	Rate	Amount in Rs.	Whether the items are alternative to items in the tender or whether they are additional items (If items are in lieu of some items in the	Whether the extra item is included in the sanctioned estimate	How the extra cost of the item is proposed to be met	Whether the extra item is included in the schedule of rate of the Division. If so reference to this item of the schedule to be given, If not data sheets should accompany the rate list	Remarks
1	2		3	4	5	6	7	8	9	10
EIRL 1	KSRRB M300- Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) MORTH Specification No. 305 (P.No. 147 /I.No. 19.60 of	Cum	995.10	382.33	**380456.58**	Additional item	No	In the revised estimate to be sanctioned later	KSRRB M300	
	Total				**380456.58**					

ಸಹಾಯಕ ಅಭಿಯಂತರರು
ಬ.ಬಿ.ಎಂ.ಪಿ. ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ಬೆಂಗಳೂರು-24

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

"EIRL Approved"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ವಿಭಾಗ ವಲಯ
ವೃತ್ತ ಬೆಂಗಳೂರು ನಗರ ಪಾಲಿಕೆ.